SOLARFLOW DEMO ENERGY

Solar PV Project Integration & Material Loading Checklist

BILL OF MATERIALS (BOM) - ROOF TYPE

1. CUSTOMER & SITE REFERENCE

Customer Name:	RAMESH PATEL	Phone Number:	90000 00001
Email Address:	demo.customer@example.com	Consumer No:	DEMO-244001
Villages:	**DEESA**	Sub Division:	**DEESA**
Channel Partner Name:	–	Dealer Name:	–
MODULE BRAND:	**APS**	MODULE WP:	**600**
No of Modules:	**6**	System Capacity (kWp):	**3.6 kWp**

2. MATERIAL ORDER SPECIFICATIONS

Roof / Shed:	**Roof**	Structure Leg Height:	**Front: 6 ft / Rear: 8 ft**
DC Cable Length:	**25 Meters**	AC Cable Length:	**25 Meters**
Estimated Invoice Value:	**₹ 1,80,000**		

3. PROCUREMENT & LOADING MILESTONES

Paper Prepared By:	**Demo Staff Birch**	Paper Prepared Date:	–
Material Loaded By:	–	Material Loaded Date:	–

4. INVERTER & EQUIPMENT SPECIFICATION

Inverter Make:	**Solax**	Inverter Serial No:	DEMO-INV-0001

5. SOLAR PANEL SERIAL NUMBERS

TOTAL: 6 PANELS

1. **DEMO-PNL-01**	2. **DEMO-PNL-02**	3. **DEMO-PNL-03**
4. **DEMO-PNL-04**	5. **DEMO-PNL-05**	6. **DEMO-PNL-06**

SOLARFLOW DEMO ENERGY

Solar PV Project Integration & Material Loading Checklist

BILL OF MATERIALS (BOM) - ROOF TYPE (EQUIPMENT CHECKLIST)

Customer: RAMESH PATEL | Consumer No: DEMO-244001 | Capacity: **3.6 kWp**

6. BOM EQUIPMENT CHECKLIST (ROOF)

#	Product Name	Qty	UOM	Integration By	Note / Remarks
1	Solar Panel	6	Nos	–	–
2	Inverter	1	Nos	–	–
3	ACDB	1	No.	–	–
4	DCDB	1	No.	–	–
5	Dc Cable	60	MTR	–	–
6	Earthing Cable	45	MTR	–	–
7	16sq MM LA cabel	35	MTR	–	–
8	Ac Cable	10	MTR	–	–
9	Isolation box+MCB	1	No.	–	–
10	Shadel	50	No.	–	–
11	Elbow	35	No.	–	–
12	Tea	7	No.	–	–
13	Wedge Anchor Fast	16	No.	–	–
14	8 aani 4 inch	4	No.	–	–
15	6 aani 6 inch	8	No.	–	–
16	jasti khila	8	No.	–	–
17	m c 4 conectar	2	No.	–	–
18	Screw/ Tape	15	No.	–	–
19	16 sq MM Round LUG	3	No.	–	–
20	4 sq MM Round LUG	3	No.	–	–
21	4 Sqmm Pin Type Lug	10	No.	–	–
22	Red/Black Sleeve	5+2	No.	–	–
23	5 aani 2inch	1	No.	–	–
24	Mid Clamp	8	No.	–	–
25	End Clamp	8	No.	–	–
26	GI Clamp	24	No.	–	–
27	u bolt+patti	16	No.	–	–
28	Chaki+Wisher	32	No.	–	–
29	Sapot pati	3	No.	–	–
30	rubar cap	8	No.	–	–
31	cabale ties	15	No.	–	–
32	Cable Tie (Nani)	36	No.	–	–
33	Earth Pit Doll	3	No.	–	–
34	40*40 Pipe Perlin	12*4	Feet	–	–
35	60*40 Pipe rafter	13*2	Feet	–	–
36	60*40 front leg	6*2	Feet	–	–
37	60*40 Rear leg	8*2	Feet	–	–
38	LA insuletar	1	No.	–	–
39	cabale tre	1	No.	–	–
40	Earthing Kit + LA	3+1	No.	–	–
41	chemical	1	No.	–	–
42	Conduite Pipe	15	No.	–	–
43	Cement	0.5	Bag	–	–
44	Reti	2	Bag (50 kg)	–	–
45	Kapachi	1	Bag (50 kg)	–	–

PREPARED BY	LOADED BY	AUTHORIZED / RECEIVED BY
Demo Staff Birch	–	–